

TRAVANCORE DEVASWOM BOARD
SABARIMALA DEVELOPMENT PROJECT
PATHANAMTHITTA
NOTICE INVITING QUOTATIONS

No.SDP/EE/Q-6 /16-17

The Executive Engineer, Sabarimala Development Project, Pathanamthitta, on behalf of the Travancore Devaswom Board, invites sealed competitive quotation for the following works from the registered contactors in Travancore Devaswom Board.

SL No	QUOTATION No	Name of work with PAC	EMD	Date of quotation
1	SDP/EE/QN-6/16/17	Quotation are invited from qualified and experienced contractors for special and traditional painting to the Pampa Ganapathy temple with Nadapandal , Subshrines and temple structures using special all guard metallic copper paint and other appropriate materials to the walls and roof structures including necessary repairs and maintenance works to the existing structure .The rate should include cost of all materials, labour charges, higher charges of equipments etc complete The quotationer has to quote rates for each item of work	2.5% of the total quoted amount	5/10/2016
2	SDP/EE/QN-7 /16-17	<p>Fabrication supply and instatllation of loading Boxes (Front & Back) with chase for Tractors :</p> <p>(A) Fabrication, Supply and Installation of loading boxes with chase for tractors comprising of Front side box having 31"x33"x33" size with 33"x31" side panel (4 nos) made with 32x32x6mm ms angle supports all around, 32x32x6mmx31" long ms angles as horizontal supports (4nos), 32x32x6mm ms angle 33" long as intermediate vertical support (1 no) and for the bottom panel of 31"x33" size (1 no) made with 75x75x6mm ms angle 31" long (2 nos) as intermediate horizontal and cladding the inner portion using 16 gauge rust protected Japan Sheet.</p> <p>(B) Rear side box having 31"x50"x31" size with 31"x50" side panel (4 nos) made with 32x32x6mm ms angle support all around, 32x32x6mmx31" ms angles as horizontal supports (4 nos) 32x32x6mm MS Angle 50" long as intermediate vertical support (1 no) and for the bottom panel of 31"x33" size (1 no) made with 75x75x6mm ms angle 31" long (2 nos) as intermediate horizontal and cladding the inner portion by using 16 gauge rust protected Japan Sheet.</p>	2.5% of the total quoted amount	

	<p>(C)</p> <p>(D)</p>	<p>Chase of 100x100 mm size box using 100x50x6 mm “C” Chanel by welding flange to flange in order to make box of size 100x100 mm (2 nos) having a total length of 173 inches, welding together using 100x50x6 mm “C” Chanel as chase for tractor in order to support the front & Back box as per standard specification.</p> <p>A provision for door in each box with necessary locking arrangements and three coats of enamel spray painting over one coat of iron primer and letter works etc complete.</p>		
--	-----------------------	---	--	--

Time of receipt of quotation up to 3 P.M 5-10-2016

TERMS AND CONDITIONS

- 1) The EMD should be in the form of deposit receipt from any of the Nationalized/Scheduled bank pledged in favour of the Executive Engineer, Sabarimala Development Project, Pathanamthitta (2) Category of contractor D class and above civil .(3) TDB reserves the right to reject any quotation without assigning any reason. (4) . If the last date of quotation happens to be a holiday ,the quotation will be received and opened in the next working day at the same time prescribed..(5) All other conditions of invitation of quotation in the TDB will be applicable to this quotation also. (6). More information are available had from the office of the undersigned on all working days during working hours

Pathanamthitta
30 - 9 -2016

G. KRISHNAKUMAR.
Executive Engineer
Sabarimala Development Project.
Pathanamthitta.
(for and behalf of Travancore Devaswom Board)