



TN No. 18/HPC/SMP/2017-18

Dated 21.10.2017

NOTICE INVITING e – TENDERS / QUOTATIONS

The High Power Committee for Implementation of Sabarimala Master Plan invites Competitive e – Tenders / Quotations from Registered Companies/Firms or Contractors of PWD, CPWD and Travancore Devaswom Board for works in **Annadhanamandapam** at **Sannidhanam Sabarimala**. For details and submission of e-tender, log on to www.etenders.kerala.gov.in. Quotations shall be submitted in sealed cover.

1. e-Tender Ref. No: T-27/HPC/SMP/2017-18 Supply, Installation, Testing and Commissioning of Dumb Waiter
2. Quotation No. Q-01/HPC/SMP/2017-18 Providing and Fixing S S Floor Gratings with Cockroach Trap of various sizes
3. Quotation No. Q-02/HPC/SMP/2017-18 Providing and Fixing Hand Wash Trough Sink of size 200mm x 500mm x 300+200 mm
4. Quotation No. Q-03/HPC/SMP/2017-18 Providing Corner Guard with Damper
5. Quotation No. Q-04/HPC/SMP/2017-18 Relocation of Bhandaram – Supply, Installation, Testing and Commissioning of Conveyor Belt System

Last date for item No. 1: 5pm on 28.10.2017. Opening : 11am on 01.11.2017

Last date for item Nos. 2,3,4&5: 5pm on 28.10.2017. Opening : 11am on 30.10.2017

For further details contact at sabarimalamasterplan@gmail.com and www.travancoredevaswomboard.org

Sd/- Member Secretary & Devaswom Commissioner
for and on behalf of the High Power Committee

Note: The quoters should submit their quotation in the enclosed format along with a covering letter before the last date of quotations ie., on 28.10.2017

Name of Work: Providing and fixing SS floor gratings with cockroach trap of various sizes in Annadhanamandapam at Sannidhanam,Sabarimala

Quotation No.Q-01/HPC/SMP/2017-18

Schedule of Items

Sl. No.	Description of Items	Quantity	Units	Rate in figures (Rs. P.)	Rate in words	Amount in Rs. P.
1	Providing and fixing of SS FLOOR GRATING WITH COCKROACH TRAP OF SIZE 300mmX300mmX75+50mm with following specifications: SS 304 1.2 mm trough and 2mm SS 304 grating; Residual clean water retaining system for hygiene and fowl smell prevention; Easy to remove and	12.00	Nos			
2	Providing and fixing of SS FLOOR GRATING WITH COCKROACH TRAP OF SIZE 600mmX300mmX75+50mm with following specifications: SS 304 1.2 mm trough and 2mm SS 304 grating; Residual clean water retaining system for hygiene and fowl smell prevention; Easy to remove and clean cockroach trap	38.00	Nos			
3	Providing and fixing of SS FLOOR GRATING WITH COCKROACH TRAP OF SIZE 1200mmX300mmX75+50mm with following specifications: SS 304 1.2 mm trough and 2mm SS 304 grating; Residual clean water retaining system for hygiene and fowl smell prevention; Easy to remove and clean cockroach trap	13.00	Nos			
4	Providing and fixing of SS FLOOR GRATING WITH COCKROACH TRAP OF SIZE 1200mmX600mmX75+50mm with following specifications: SS 304 1.2 mm trough and 2mm SS 304 grating; Residual clean water retaining system for hygiene and fowl smell prevention; Easy to remove and clean cockroach trap	28.00	Nos			
Total Amount						

Signature of Bidder:

Name & Address of Bidder:

Name of Work: Providing and fixing Hand wash trough sink in Annadhanamandapam at Sannidhanam, Sabarimala

Quotation No.Q-02/HPC/SMP/2017-18

Schedule of Item

Sl. No.	Description of Item	Quantity	Units	Rate in figures (Rs. P.)	Rate in words	Amount in Rs. P.
1	Providing and fixing of HANDWASH TROUGH SINK OF SIZE 2000mmX500mmX300+200mm with following specifications: 16 SWG SS 304 Sink Unit with 20 SWG SS 304 with Apron	48.00	Nos			
Total Amount						

Signature of Bidder:

Name & Address of Bidder:

Name of Work: Providing CORNER GUARD WITH DAMPER in Annadhanamandapam at Sannidhanam,Sabarimala

Quotation No.Q-03/HPC/SMP/2017-18

Schedule of Item

Sl. No.	Description of Item	Quantity	Units	Rate in figures (Rs. P.)	Rate in words	Amount in Rs. P.
6	Providing and fixing of CORNER GUARD WITH DAMPER(KITCHEN, STORE & DINING AREA): SS 304 20 SWG with load transfer construction to prevent shock transfer to tiles	240.00	m			
Total Amount						

Signature of Bidder:

Name & Address of Bidder:

SABARIMALA MASTER PLAN

Name of work: SMP-Relocation of Bhandaram at Sannidhanam,Sabarimala-Supply,Installation,Testing and Commissioning of Conveyor Belt system

Quotation No.-04/HPC/SMP/2017-18

Schedule of Items

Sl.No.	Description of items	Qty.	Unit	Rate in Figures Rs. P.	Rate in words	Amount in Rs. P.
1	Conveyor belt-A: Supplying and erecting main 3 ply conveyor belt 10mm thickness 53 meter length with head drum 12'' X 8mm x 40'' ms pipe with 2 ½ '' polish round 60''length (1No), back drum 12'' X 8mm X 40'' ms pipe with 2 ½ '' polish round 54''length (1No), gravity side drum 8'' X 8mm X 40'' ms pipe with 2 ½ '' polish round 54''length (2Nos), gravity center 10'' X 8mm X 40'' ms pipe with 2 ½ '' polish round 54''length (1Nos), total (5Nos) drums, 1Nos gear box SMSR type, 10hp motor (1No), pully (1Nos),2 ½ bearing block(10Nos) with bearing Fabricaed frame made 4''X 2'' c-channel 6mm and c-channel frame, size length 25 meter. including 3 way type roller stand with roller(27Nos) , roller 3'' X 13'' size (81Nos), return roller 2 ½ '' X 40'' of length (12Nos),side roller (4Nos) including one coat of both primer and painting with sytetic enamel paint applied, nut bolt including cost of all material labour charge etc. complete.	1.00	No.			
2	Conveyor belt-B: Supplying erecting and Fabrication frame made 4''X 2'' c-channel 6mm and c-channel frame, size length 18 meter. Including 3 way type roller stand with roller(20Nos) , roller 3'' X 13'' size (60Nos), return roller 2 ½ '' X 40'' of length (9Nos),side roller (4Nos) conveyor belt 3 ply 10mm thickness 39 meter length, head drum 12'' X 8mm x 40'' ms pipe with 2 ½ '' polish round 60''length (1No), back drum 12'' X 8mm X 40'' ms pipe with 2 ½ '' polish round 54''length (1No), gravity side drum 8'' X 8mm X 40'' ms pipe with 2 ½ '' polish round 54''length (2Nos), gravity center 10'' X 8mm X 40'' ms pipe with 2 ½ '' polish round 54''length (1No), total (5Nos) drums, 1No gear box SMSR type, 10hp motor (1Nos), pully (1Nos),2 ½ bearing block with bearing(10Nos) including one coat of both primer and paint will be applied, nut bolt including cost of all material labour charge etc. complete.	1.00	No.			

3	Bucket Elevator: Supplying,erecting and Fabrication frame made 4''X 2'' c-channel 6mm and c-channel frame, size length 6 meter. stain steel bucket (40Nos) return roller 2 ½ '' X 40'' of length (12Nos),side roller (4Nos) conveyor belt 3 play 12mm thickness 13 meter length, head drum 12'' X 8mm X 40'' ms pipe with 2 ½ '' polish round 60''length (1No),back drum 12'' X 8mm X40'' ms pipe with 2 ½ '' polish round 54''length (1No), 1Nos gear box SMSR type, 5hp motor (1No), pully (1No),2 ½ bearing block with bearing (4Nos) including one coat of both primer and paint will be applied, nut bolt including cost of all material labour charge etc. complete.	1.00	No.			
4	Conveyor belt-C: Supplying erecting and Fabrication frame made 4''X 2'' c-channel 6mm and c-channel frame, size length 10 meter. Including 3 way type roller stand with roller(11Nos) , roller 3'' X 13'' size (33Nos), return roller 2 ½ '' X 40'' of length (4Nos),side roller(4Nos), conveyor belt 3 play 10mm thickness 23 meter length, head drum 12'' X 8mm x 40'' ms pipe with 2 ½ '' polish round 60''length (1No), back drum 12'' X 8mm x 40'' ms pipe with 2 ½ '' polish round 54''length (1No), total (2Nos) drums, 1No gear box SMSR type, 5hp motor (1No), pully (1No),2 ½ bearing block with bearing including one coat of both primer and paint will be applied, nut bolt including cost of all material labour charge etc. complete.	1.00	No.			
5	Poly carbonate sheet roofing: Roofing conveyor belt with good quality polycarbonate sheets 0.8mm thick or nearest available size including providing and fixing roof truss using B class GI pipe of 100 to 25mm dia including fabrication charges cost and conveyance of materials erection charges etc. complete As per the Engineer in charge	59.20	Sq.m			
6	Storage tank & Tank and chute: Supplying and providing Stainless steel 1.18mm dia mouth and transferring tunnels storing tank of capacity 5' X 4' X 3' including supporting C-channel, square pipes , stain steel sheet etc. complete including cost of all material, erection charge, conveyance,labour charge etc. complete. As per the Engineer in charge	1.00	No.			
7	Electrical: Electrification including wiring,earthing cost of starter etc.including cost of all material, erection charge, conveyance,labour charge etc. complete.as per the Engineer in charge	1.00	No.			
						Total Amount

Signature of Bidder:

Name & Address of Bidder: