

# TRAVANCORE DEVASWOM BOARD

## WORK DEPARTMENT

### ASSISTANT ENGINEER'S OFFICE, THIRUVALLA

aethiruvalla@gmail.com

### NOTICE INVITING SHORT QUOTATIONS

Competitive sealed and separate quotations are invited by the undersigned on behalf of the Travancore Devaswom Board from registered civil contractors of the Travancore Devaswom Board.

Last date/time of receipt of filled up quotation forms: **24/07/2023 up to 1PM**

Date and time of opening of quotation: **24/07/2023 up to 3 PM**

Class of contractor: D class and above

SI No.	Quotation No	Name of Work	PAC Rs.	E M D Rs.	Completion period
1	AE TRVL-Q-26	Sree Vallabha Devaswom in Thiruvalla group, "Parihara kriyakal" renovation of "Planamskaram" area and certain other works.	--	2.5% of total quoted amount.	Should be completed on or before 5.8.2023

The EMD Should be in the form of Deposit receipt from any of the Nationalised/ Scheduled banks pledged in favour of the Executive Engineer, TrvancoreDevaswom Board, Mavelikkara.

The quotation should be given in the appended format.

The undersigned reserves the right to accept or reject the quotation without assigning any reason.

The work can be done only between 10AM to 5 PM every day except Thursday and Sunday.

Works cannot be done on Thursday and Sunday. The workers should obey the temple customs.

All other conditions/rules in respect of inviting quotations are the same as those currently prevailing in this department. Details are available from this office during office hours on all working days.

Office of the Assitant Engineer  
Thiruvalla

sd/-  
Assistant Engineer

20/07/2023Thiruvalla

**TRAVANCORE DEVASWOM BOARD**  
**ITEM RATE QUOTATION SCHEDULE**

**Name of work: Sree Vallabha Devaswom in Thiruvalla group-"Parihara kriyakal"- Renovation of "Pala namaskaram" area and certain other works**

SI No	DESCRIPTION	Quantity	Unit	Rate Quoted	Total
1	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-In-Charge. In cement mortar	13	M3		
2	Disposal of building rubbish/ malba/ similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved	13	M3		
3	Taking out doors, windows and clerestory window shutters (steel or wood ) including stacking within 50 metres lead:Of area 3 sq. metes and below	9	Each		
4	Sand blasting, filling the gaps and cleaning the ornamental works of ashlar pillars	12	Each		
5	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works (For providing copper sheet of pathy in front of sreecovil without connect to sreecovil)	130	Kg		
6	Replacing the bottom portion of the rafter (1 No) with common dove tail joint having 50 cm length (appx) in its original measurement with teak wood. In cluding all labour charges etc complete as per the direction of Engineer in Charge	1	No		
7	Attending repairs to the copper sheet of pathy in front of sreecovil including dismatling and refitting after closing the leakages with Mseal and as per the direction of Engineer in Charge	1	Job		
<b>Total</b>					
<b>Add .....% GST</b>					
<b>Grand Total</b>					

**Special Conditions**

1. All conditions prevailing in the department will also applicable to this quotation.
2. The work can be executed between 10 am and 5 pm in all days except Sunday and ~~Thursday~~ *Thursday*
3. The work should be completed in all respects on or before 05-08-2023

Name and Signature of Contractor